PRELIMINARY SITE LIGHTING AND PHOTOMETRIC PLAN
ROSEVILLE CONFERENCE CENTER HOTELS
SHEET 6 OF 31
251 CONFERENCE CENTER DRIVE

DC EXHIBIT N

LUMINAIRE SCHEDULE

CALLOUT	SYMBOL	LAMP	DESCRIPTION	BALLAST	MOUNTING	MODEL	VOLTS	NOTE 1	NOTE 3	QUANTITY	IES FILE
1TFTM		(1) LED,	DSX2 LED P1 40K T5W MVOLT	ELECTRONIC	POLE	Lithonia Lighting, DSX2 LED P1 40K T5W MVOLT	120V 1P 2W	LED DRIVER,	/2/2017 11/9/2017 SCALED PHOTOMETRY TYPE VS, BUG RATING: B5 – U0 – G3 19548.4 0 , 0 140 3, 1.2, 0.5 0, 0, 0 ARM MOUNT D-Series Area Size 2 66207eb1-dba3-4cc8-9d33-b2634f83c131 NOTE: DATA SHOWN IS ABSOLUTE FOR THE SAMPLE PROVIDED. 24843 70 120.0 VOLTS, 207.4 WATTS, 1.73 AMPS AMBIENT: 25.2	24	DSX2_LED_P1_40K_T5W_MVOLT

NO SCALE — LITHONIA DSX2 LUMINAIRE

MAX SITE LIGHT HEIGHT 25' INCLUDING BASE AND FOUNDATION

TYPICAL LIGHT DETAIL

GENERAL PHOTOMETRIC SCHEDULE

AVERAGE FOOT-CANDLES	1.49
MAXIMUM FOOT-CANDLES	3.9
MINIMUM FOOT-CANDLES	0
MINIMUM TO MAXIMUM FC RATIO	0.01
MAXIMUM TO MINIMUM FC RATIO	98.71
AVERAGE TO MINIMUM FC RATIO	37.94

City of Roseville Approval

MORTON & PITALO, INC.
CIVIL ENGINEERING • LAND PLANNING • LAND SURVEYING
600 Cooklige Drive, Suite 140 • Folsom, CA 95630
phone: 916.984.7621 • fax: 916.984.9617
web: www.mpengr.com

CONSULTANT

APPROVALS

NO	DATE	DESCRIPTION

REVISIONS

BENCH MARK

COMPUTED BY

DESIGNED BY

DRAWN BY

PROJECT ENGINEER

PROJECT

ROSEVILLE CONFERENCE CENTER HOTELS
251 CONFERENCE CENTER DRIVE
ROSEVILLE, CA

DRAWING
PRELIMINARY SITE LIGHTING AND PHOTOMETRIC PLAN

DATE	SHEET
JUNE 15, 2023	6
SCALE: 1" = 30'	OF 31
JOB NUMBER: 22-0061-00	

NOT FOR CONSTRUCTION

Dwg: N:\2022\22-0061-00\CONFERENCE CENTER HOTELS, ROSEVILLE\ED\DWG\PLAN\WORKING\220061-PSI SITE LIGHTING.DWG | Saved: 06-16-23 09:41am | TADAMS